BRUHAT BANGALORE MAHANAGARA PALIKE

DASARAHALLI PROJECT DIVISION

Schedule - B

Name of work:- Additional works to yoga center (Phase -2) at Sy No.33 Mallasandra in ward No.13

Name of the Contractor:Technical Manager, KRIDL

Sl No	Description of Work	Unit	Sanctioned	
			Quantity	Rates in Rs.
1	KSRRB 200-8. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. MORTH / Chapter 2 complete as per directions of the engineer in charge of the work	Sqm	1125.00	7.84
2	Excavation in Soil with Dozer: KSRRB M300-11. Excavation for road way in all types of soil by mechanical cum means including cutting and pushing the earth to site of embankment including trimming bottom and side slopes in accordance with requirements of lines, grades and cross sections complete as per specifications. MORTH Specification No. 301 complete as per directions of the engineer in charge of the work	Cum	393.75	88.86
3	Earthwork in surface excavation in ordinary soil for leveling and lowering the ground manually (Other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled including breaking of clods and neatly dressed as per specifications. complete as per directions of the engineer in charge of the work	Cum	562.50	324.91
4	Earthwork excavation by manual means for foundation of buildings, culverts, water supply and sanitary lines and electrical conduits etc, either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. including breaking of clods complete as per specifications complete as per directions of the engineer in charge of the work	Cum	1293.60	366.47
5	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. complete as per directions of the engineer in charge of the work	Cum	384.48	488.56

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Scanned by CamScanner

	Excavation 1.5m and above in width in soft rock without blasting for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches not exceeding 1.5 m. in depth, stacking the excavated stuff from edges of excavation with lead upto 50m including cost of explosives, labour and HOM of equipment complete as per specifications. complete as per directions of the engineer in charge of the work	Cum	94.25	1267.84
7	Providing and injecting chemical emulsion for Pre constructional Anti-Termite Treatment, creating continuous chemical barrier underand around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits, with chloropyriphos emulsifiable concentrates of 20% concentration, including cost of chemical, diluting in water to one percent concentration, labour, HOM of equipments, complete as per specifications. (Plinth area of the building at ground floor only shall be measured) complete as per directions of the engineer in charge of the work	Sqm	1388.88	134.60
8	Providing and Filling in foundation with granite / trap cum broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead upto 50m.and lift of 1.5m,complete as per specifications, (PWP,IWTD) SR Bangalore Circle 2014. specification. complete as per directions of the engineer in charge of the work	Cum	139.28	2762.58
9	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per directions of the engineer in charge of the work	Cum	88.13	6594.11
10	Providing and constructing granite / trap / basalt size stone masoniy in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. complete as per directions of the engineer in charge of the work	Cum	82.48	6540.53

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

CONTRACTOR

Executive Engineer
Project division
Dasarahalli Zone, BBMP

Scanned by CamScanner